



# Maine Turnpike Authority Schedule of Items

## West Gardiner Travel Plaza, Truck Parking Expansion

Item No.	Description	Quantity	UOM
201.11	Clearing	1.50	AC
203.20	Common Excavation	6,181.00	CY
203.24	Common Borrow	9,512.00	CY
203.25	Granular Borrow	760.00	CY
304.09	Aggregate Base Course - Crushed	1,475.00	CY
304.10	Aggregate Subbase Course - Gravel	7,270.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	2,170.00	TON
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size, Surface	1,090.00	TON
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size, Base	1,090.00	TON
409.15	Bituminous Tack Coat, Applied	1,300.00	GAL
419.30	Sawing Bituminous Pavement	690.00	LF
606.353	Delineator Post	3.00	EA
606.354	Remove and Reset Delineator Post	16.00	EA
607.2326	Pipe Entry Gate - Remove and Reset	1.00	EA
610.18	Stone Ditch Protection	20.00	CY
613.319	Erosion Control Blanket	735.00	SY
615.0701	Loam - Plan Quantity	230.00	CY
618.1401	Seeding Method Number 2, Plan Quantity	18.00	UNIT
618.15	Temporary Seeding	25.00	LB
619.1201	Mulch, Plan Quantity	18.00	UNIT
619.1202	Temporary Mulch	1.00	LS
620.58	Erosion Control Geotextile	60.00	SY
626.112	Precast Junction Box	6.00	EA
626.2203	2 Inch Non-metallic Conduit - Schedule 40 PVC	1,110.00	LF
626.2204	2 Inch Non-metallic Conduit - Schedule 80 PVC	2,400.00	LF
626.2206	4 Inch Non-metallic Conduit - Schedule 80 PVC	1,000.00	LF
626.32	24 Inch Foundation	4.00	EA
627.18	12 Inch Solid White Pavement Marking Line	42.00	LF
627.711	White or Yellow Pavement Marking Line - Plan Quantity	5,000.00	LF
627.75	White or Yellow Pavement & Curb Marking	111.00	SF
629.05	Hand Labor, Straight Time	20.00	MH
631.12	All Purpose Excavator (including operator)	10.00	HR
631.171	Truck - small (including operator)	10.00	HR
631.36	Foreman	30.00	HR
634.160	Highway Lighting	1.00	LS
634.208	Remove and Reset Light Standard	6.00	EA
634.2156	#.6 AWG THHN Wire	30.00	CLF



## Maine Turnpike Authority Schedule of Items

Item No.	Description	Quantity	UOM
634.2161	#10 AWG THHN Ground Wire	15.00	CLF
634.2254	Light Standard, Type DD	3.00	EA
634.2255	Light Standard, Type DD Double Arm	1.00	EA
645.109	Remove and Reset Sign	2.00	EA
645.271	Regulatory, Warning, Confirmation and Route Assembly Sign, Type I	21.00	SF
652.312	Type III Barricades	2.00	EA
652.33	Drum	20.00	EA
652.35	Construction Signs	70.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
656.50	Baled Hay, in Place	20.00	EA
656.60	Temporary Berms	1,000.00	LF
656.62	Temporary Slope Drains	200.00	LF
656.632	30 inch Temporary Silt Fence	1,350.00	LF
659.10	Mobilization	1.00	LS