



Maine Turnpike Authority Schedule of Items

Pavement Rehabilitation and Guardrail Improvements Mile 44.0 to Mile 51.2

Item No.	Description	Quantity	UOM
202.202	Removing Pavement Surface	223,500.00	SY
202.2021	Removing Pavement Surface - Bridge Deck	5,710.00	SY
202.2026	Removing Pavement Surface - Drainage Paths	4,630.00	SF
202.205	Rumble Strips	25,910.00	EA
203.2	Common Excavation	150.00	CY
203.241	Common Borrow, Truck Measure	235.00	CY
205.51	Widening of Existing Shoulder, Plan Quantity	100.00	LF
205.52	Widening of Existing Shoulder For Truck Turnout	2.00	EA
304.1	Aggregate Subbase Course - Gravel	120.00	CY
403.209	Hot Mix Asphalt, 9.5 mm Norminal Maximum Size (sidewalks, drives, islands & incidentals)	200.00	TON
403.21	Hot Mix Asphalt, 9.5 mm Norminal Maximum Size	19,560.00	TON
403.2101	Hot Mix Asphalt, 9.5 mm Norminal Maximum Size - Bridge Deck	504.00	Ton
409.15	Bituminous Tack Coat - Applied	6,800.00	GAL
409.151	Bituminous Tack Coat - Applied, Bridge	179.00	GAL
419.3	Sawing Bituminous Pavement	200.00	LF
459.06	Bituminous Concrete Waterway	37.00	EA
470.08	Berm Drop Off Correction - Grindings	3,500.00	TON
508.14	High Performance Waterproofing Membrane	1.00	LS
518.64	Thoroc 10-60 Rapid Set Motar (50 lb. Bag)	30.00	EA
518.8	Partial Depth Concrete Deck Repairs	2,584.98	SF
518.81	Full Depth Concrete Deck Repairs	40.06	SF
524.3	Temporary Protective Support	4.00	EA
527.303	Energy Absorbing System (CAT) - Remove and Reset	2.00	EA
603.155	12 Inch Reinforced Concrete Pipe - Class III	9.00	LF
604.184	Rebuild Catch basin to Grade - Type II	1.00	EA
604.186	Rebuild Catch Basin to Grade - Type IV	33.00	EA
606.178	Guardrail Beam	300.00	LF
606.24	Guardrail Type 3d - Single Rail	100.00	LF
606.2401	Guardrail Type 3d - Double Rail	600.00	LF
606.353	Delineator Post	7.00	EA
606.354	Remove and Reset Delineator Post	7.00	EA
606.3605	Guardrail - Remove, Modify and Reset, Single Rail	225.00	LF
606.3606	Guardrail - Remove, Modify and Reset, Double Rail	1,150.00	LF
606.3621	Guardrail Adjust, Single Rail	1,000.00	LF
606.3631	Guardrail - Remove and Dispose	325.00	LF
606.471	Single Offset Block - W-Beam	40.00	EA



Maine Turnpike Authority Schedule of Items

Item No.	Description	Quantity	UOM
606.48	Single Galvanized Steel Post	25.00	EA
606.754	Widen Shoulder For Guardrail 350 Flared Terminal	4.00	EA
606.8	Guardrail 350 FLEAT Terminal	4.00	EA
606.92	Guardrail 350 FLEAT MT - Remove and Stack	4.00	EA
613.319	Erosion Control Blanket	3,165.00	SY
615.07	Loam	320.00	CY
618.14	Seeding Method Number 2	55.00	UNIT
619.12	Mulch	55.00	UNIT
619.1202	Temporary Mulch	1.00	LS
627.712	White or Yellow Pavement Marking Line	157,700.00	LF
627.713	Broken White Pavement Marking Line	76,000.00	LF
627.761	Temporary Pavement Marking Line, White or Yellow	76,000.00	LF
627.802	Temporay Raised Pavement Markers	6,000.00	EA
629.05	Hand Labor, Straight Time	15.00	HR
631.1	Air Compressor (including operator)	2.00	HR
631.11	Air Tool (including operator)	2.00	HR
631.12	All Purpose Excavator (including operator)	5.00	HR
631.17	Truck - Large (including operator)	5.00	HR
631.36	Foreman	10.00	HR
645.105	Remove and Stack Sign	2.00	EA
645.109	Remove and Reset Sign	1.00	EA
652.3	Flashing Arrow Board	4.00	EA
652.331	Drum	1.00	LS
652.35	Construction Signs	3,140.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.41	Portable - Changeable Message Sign	2.00	EA
652.411	Portable - Changeable Message Sign with Radar Unit	1.00	EA
656.5	Baled Hay, in place	260.00	EA
656.6	Temporary Berms	1,000.00	LF
656.62	Temporary Slope Drains	200.00	LF
656.632	30 Inch Temporary Silt Fence	2,300.00	LF